MYSORE DIVISION.

The 5th January 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 25th January 1897, for restoring the Kempasagara tank, registered No. 26, Gundlupet taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at the Division office between the hours of 11 A. M. and 5 P. M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kempasagara tank, registered No. 26, Gundlupet taluk", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	*Per.*	*Quantity.*
Bund.		
Earthwork	C. yd.	11,160
Old stone work dismantling and re-building with 1 foot jelly	„	300
New stone work	„	2,732
R. No. stone with numbers, fixing, &c.	No.	1
Gauge stone	„	1
Grade stones with opposite and bottom slabs and fixing with numbers complete	„	31
B. M. stones with numbers, &c.	„	2
Date stone	„	1
Breach.		
Earthwork	C. yd.	40,164
New stone work	„	1,710
Bailing water, blasting rock, &c.	Lump sum.	
Sluice No. II earthwork	C. yd.	1,047
Surki concrete	C. ft.	2,022
Brick in surki mortar	„	1,669
Dismantling and fixing gibbets	Lump sum.	
Plastering with surki mortar	Sqr.	5·58
Slabs stones	C. ft.	219
Cut stone, cross gibbet with plug hole	Lump sum.	
Rough stone work	C. yd.	12
Plug and gearing rod	Lump sum.	
Weir 135.		
Earthwork and gravel work	C. yd.	1,833
Brick in surki mortar	C. ft.	2,571
Burnt stone do	„	1,052
Slab stones	„	135
Plastering with surki mortar	Sqr.	3·50
Pointing with do	„	238
Rough stone work	C. yd.	163
Blasting rock	„	256
Jungle clearing and benching out rock	Lump sum.	